MEMORANDUM ADDENDUM#2

IFB# 21-002 City of Fairburn

Rivertown Road Pedestrian Improvements Project

Questions & Responses:

- 1. Are there profiles or a grading plan to determine earthwork quantities?
- It appears that there are two brick mailboxes one in base bid and one in the alternate 1. Will the contractor be responsible for rebuilding these in kind?
 The new sidewalk should be installed around the brick mailboxes. A gradual transition to and from the prick mailboxes.
 - The new sidewalk should be installed around the brick mailboxes. A gradual transition to and from the back of curb will be required.
- 3. The detail for the retaining wall appears for a cut wall. Some sections will require a fill wall. Is there a detail for these walls?
 - No, other detail is provided. The successful Contractor may provide an alternative to the detail provided in the plans for review and consideration if necessary.
- 4. Will contractor be compensated for actual quantities? Yes. This is not a lump sum project.
- 5. Will there be a railing where the catch basin is open in the back?

 It is not anticipated. No railing is required unless the drop is over 30". The contractor is responsible for field verifying grade and letting the City know if a railing is required or not.
- 6. Are fire hydrants being adjusted to grade or are they being relocated outside the work area. If fire hydrants are not conflicting with the sidewalk, they can just be reset at the new grade. If the fire hydrants are conflicting with the new sidewalk, they need to be relocated out of the way and reset to grade.

End of Addendum